

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21115-00-00 Spot: C S2SE
Sec: 13 Twnshp & Dir: 32 S Rng & Dir: 2 W
Feet: 660 frm N/S: S Feet: 1320 frm E/W: E
Lease/Unit Name: YOCAM Well Number: 1
County: HARPER Total Vertical Depth: 4460 feet

Operator License No.: 101
Operator Name: Kansas Corporation Commissio
Address: 130 South Market, Room 2078
Wichita, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 261
Production: Size 4.5 feet: 4038

Well Type: GAS UIC Docket No: Date/Time to Plug: 09/28/1999 8:00 AM
Plug Co. License No.: 100 Plug Co. Name: Kansas Corporation Commission
Proposal Received from: Company Name:
OpRepPhoneNo:

Were: See actual plugging report- Perfs. 3445-3448

Plugging Proposal Received By: Steve VanGieson, KCC WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/28/1999 10:00 AM

Actual Plugging Report:

FEE FUND PLUGGING Pmpd. 30 sx cmt. Plug to close perfs TOC 2820 Perf @1300' & pmpd. 50 sx cmt, inside & outside 4 1/2" Perf @850' & pmpd. 50 sx cmt inside & outside 4 1/2" perf @ 310' & cir. cmt to surf. Ckd. Plug 9-29, cmt fell 50' topped off cmt. cut off head & closed

Remarks: Copeland Acid & Cement-Common Cement FEE FUND PLUGGING-SEE FILE FOR DETAILED P/A-PLUG TIME
Anhydrite Plug: No BottomPlug: DakotaPlug: No
Plugged through:

I (did) / did not observe this plugging.

Signed

(TECHNICIAN)

ok
Det by KA