

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

5-21

API NUMBER: 15-077-20531-0000

C-SE \ SECTION 4 TOWNSHIP 32 RANGE 9 W

OPERATOR LICENSE # 5429
OPERATOR Hays Oil and Gas
NAME P.O. Box 108
ADDRESS Attica KS. 67009

1320 FEET FROM S SECTION LINE
1320 FEET FROM E SECTION LINE
LEASE NAME: Bob # 2
COUNTY Harper
WELL TOTAL DEPTH: 4336' *140.92*
PIPE: 4 1/2 @ 4360'
SURFACE CASING 8 5/8 @ 214'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Clarke Corporation
ADDRESS: Medicine Lodge KS. LICENSE: 5105

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: _____

PLUGGING PROPOSAL RECEIVED FROM: Alan Vrital
COMPANY NAME: Clarke Corporation PHONE: _____
WERE: Perfs 4313-23
CIBP @ 4200
35 sks @ 1325'
35 sks @ 854'
Circulate cement from 265'

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()
COMPLETED: HOUR: 1500 DAY: 21 MONTH: 5 YEAR: 1999

9-3-99

ACTUAL PLUGGING REPORT: A CIBP was set at 4208. The casing was recovered from 2700' and pulled from the wellbore. The tubing was run to 1323' where 35 sks of cement was spotted. The tubing was pulled to 854' where 35 sks of cement was spotted. The tubing was pulled to 265' where cement was circulated to surface.

REMARKS: Allied Cementing 60/40 Poz 4 & gel

I DID OBSERVE THIS PLUGGING.

[Signature]
Steve VanGieson

FORM CP-2/3
REV. 3/90

INVOICED

DATE 9-14-99

INV. NO. 60519

(2)