

1 040381

12-19

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,016-0000

SW SW NW, SEC. 25, T 32 S, R 15 W/R

2970 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Cline "D" Well # 1

Operator: TXO Production Corporation

County Barber 131.04

Name & Address 1660 Lincoln, Suite 1800

Well Total Depth 4032 feet

Denver, CO 80264

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:30 a.m. Day: 19 Month: 12 Year: 1989

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 3708' PBD 3684' CIBP at 3500' Perfs at 3582-92, 2655-60'

1st plug sand back to 2600' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 19 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 2600' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2200' of 4 1/2" casing.
(If additional description is necessary, use BACK of this report.)

RECEIVED
STATE CORPORATION COMMISSION
12-21-89
DEC 21 1989

CONSERVATION DIVISION
Wichita, Kansas

I (did / ~~did not~~) observe this plugging.
INVOICED

Signed Stephen J. Pfeifer
(TECHNICIAN)

DATE 1-3-1990

WV. NO. 26873