

1 010257

JUN 23 1987

API NUMBER 15-007-21,527-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE, SEC. 19, T 32 S, R 15 W/E
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Lease Name Marsh Ranch Well # 2

Operator: Gore Oil Company
Name & Address 125 North Market, Suite 1750
Wichita, KS 67202

County Barber 157.24
Well Total Depth 4838 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 323

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 11:10 a.m. Day: 23 Month: 6 Year: 19 87

Plugging proposal received from Gary Ray

(company name) Gore Oil Company (phone) 316-263-3535

were: 4 1/2" at 4836' PBTD 4805' Perfs at 4770-80'

1st plug sand back to 4628' and dumped 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 15 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Plugging Proposal Received by Paul and Jack Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:50 a.m. Day: 23 Month: 6 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug sanded back to 4628' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 15 sx gel, 1 sx hulls, released wiper plug and pumped 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 30 1987
6-30-87

Maximum pressure 350 psi and shut in 150 psi:ene

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2245' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(operator) observe this plugging.

DATE 6-7-1-87

Signed Jack Luthi (TECHNICIAN)

INV. NO. 17387