

1
010256

JUN 23 1987

API NUMBER 15-007-21,570-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

N/2 N/2, SEC. 20, T 32 S, R 15 W/E
4620 feet from S section line
2640 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Lease Name Marsh Ranch Well # 3

Operator: Gore Oil Company
Name & Address: 125 North Market, Suite 1750
Wichita, KS 67202

County Barber 157.98

Well Total Depth 4861 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 219

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 12:30 p.m. Day: 23 Month: 6 Year: 1987

Plugging proposal received from Gary Ray

(company name) Gore Oil Company (phone) 316-263-3535

were: 4 1/2" at 4858' PBD 4850' Perfs at 4806-16'

1st plug sand back to 4695' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Paul and Jack Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:05 p.m. Day: 23 Month: 6 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 4695' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

wiper plug and pumped 100 sx cement.

Maximum pressure 200 psi and shut in 100 psi.

JUN 30 1987
6-30-87
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2468' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

Signed Jack Luthi (TECHNICIAN)

DATE 7-1-87

INV. NO. 17388