

9-12 22377 95 R

To: 1 040564  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 13-007-23,377-0000

SE SE SE, SEC. 21, T. 32 S, R 15 W&E

330 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Marsh Trust Well # 1 "A"

Operator: Pickrell Drilling Company, Inc.

County Barber 128.37

Name:  
Address 110 N. Market, Suite 205  
Wichita, KS 67202

Well Total Depth 3950 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 227

Abandoned Oil Well Gas Well Input Well SMD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123

Address 110 N. Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 8 a.m. Day: 12 Month: 9 Year: 19 91

Plugging proposal received from Dale Faulkerts

(company name) Pickrell Drilling Company, Inc. (phone) 316-262-8427

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 825'

1st plug at 825' with 50 sx cement, 2nd plug at 260' with 40 sx cement,

3rd plug at 40' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10 a.m. Day: 12 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 825' with 50 sx cement,

2nd plug at 260' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
7-18-91  
SEP 18 1991

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

(XXX / did not) observe this plugging.

Signed *Steve Pfeifer* (TECHNICIAN)

INVOICED

DATE 10-7-91

INV NO. 33283

FOR KCC USE:

EFFECTIVE DATE: 8-31-91

DISTRICT # 1

SEAT: Yes No

State of Kansas

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

FORM C-1 7/91

FORM MUST BE TYPED  
FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

Expected Spud Date 8 - 30 - 91  
month day year

Spot SE SE SE Sec 21 Twp 32 S Rg 15 East West

OPERATOR: License # 5123  
Name: Pickrell Drilling Company, Inc.  
Address: 110 N. Market, Suite 205  
City/State/Zip: Wichita, Kansas 67202  
Contact Person: Don Beauchamp  
Phone: 316-262-8427

330 feet from South / ~~N&S~~ line of Section  
330 feet from East / ~~E&W~~ line of Section  
IS SECTION X REGULAR IRREGULAR?

CONTRACTOR: License #: 5123  
Name: Pickrell Drilling Co., Inc.

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Barber

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Enh Rec ... Infield X Mud Rotary  
X Gas ... Storage X Pool Ext. ... Air Rotary  
... DWVO ... Disposal ... Wildcat ... Cable  
... Seismic: ... # of Holes ... Other

Lease Name: Marsh Trust Well #: #1 "A"  
Field Name: Deerhead

If DWVO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Is this a Prorated/Spaced Field? ... yes X no  
Target Formation(s): Elgin Sand

Directional, Deviated or Horizontal wellbore? ... yes X no  
If yes, true vertical depth: \_\_\_\_\_  
Bottom Hole Location: \_\_\_\_\_

Nearest lease or unit boundary: 330'  
Ground Surface Elevation: 1870 feet MSL

Water well within one-quarter mile: ... yes X no  
Public water supply well within one mile: ... yes X no

Depth to bottom of fresh water: 130'  
Depth to bottom of usable water: 130'

Surface Pipe by Alternate: X 1 2  
Length of Surface Pipe Planned to be set: 250'

Length of Conductor pipe required: None  
Projected Total Depth: 4000'

Formation at Total Depth: Oread  
Water Source for Drilling Operations: \_\_\_\_\_ well \_\_\_\_\_ farm pond X other

DWR Permit #: \_\_\_\_\_  
Will Cores Be Taken? ... yes X no

If yes, proposed zone: \_\_\_\_\_

Expires 2-26-92

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:

Pusher Dale Faulkner  
SPUD DATE 9-6-91 INIT. S.P.  
LENGTH SURFACE PLANNED 225 + of 858"  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 858 @ 227' CONDUCTOR  
ANHYDRITE T- B-825 ELEVATION  
TD 3950 FORMATION  
RAN PIPE @ DV TOOL ALT II DONE  
SX SX Y N  
Arbuckle Plug @ Ft. W/ SX  
Hug./Council @ Ft. W/ SX  
1 Anhydrite Base @ 825 Ft. W/ 50 SX  
1/2 Base Anyh. @ Ft. W/ SX  
1/2, 1/2 Plug @ Ft. W/ SX  
2 Bottom Surface @ 260 Ft. W/ 40 SX  
3 40' Plug @ 40 Ft. W/ 10 SX  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX  
WATER WELL SX (Irr. Well Pond  
TECHNICIAN S.P. DATE 9-10-91 Hauling  
TYPE OF CEMENT 60/40/20 @ 2 lb  
STARTING TIME 8:00 (AM/PM) DATE 9-12-91  
COMPLETION TIME 10:00 (AM/PM) DATE 9-12-91  
CEMENT COMPANY A. H. H. H.