

1 030862

9-28-87 15-007-21965-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill completion 12/12/84

NE NE SE, SEC. 34, T 32 S, R 15 W E

2310 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9869

Lease Name DeGeer Well # 1

Operator: Chapman Energy, Inc.

County Barber 154.54

Name: Willard French/C/O Raymond Supply Co.

Address 5730 North Broadway

Well Total Depth 4755 feet

Wichita, KS 67219

Conductor Pipe: Size feet

Surface Casing: Size 13 3/4 feet 295

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:30 p.m. Day: 28 Month: 9 Year: 19 87

Plugging proposal received from Dallas Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4754' Perfs at 3625-34' PRTD 3675' Elevation 1981' GL

1st plug pump 25 sx cement at perforations,

2nd plug squeeze with 4 sx hulls, 15 sx gel, 75 sx cement, 15 sx gel, 1 sx hulls, and 225 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7:15 p.m. Day: 28 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx cement at perforations,

2nd plug squeezed with 4 sx hulls, 15 sx gel, 75 sx cement, 15 sx gel, 1 sx hulls, and 225 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 300 psi and shut in 200 psi.

OCT 2 1987 10-2-87

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2850' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

I (XXX) did not observe this plugging.

Signed Steve Whimont (TECHNICIAN)

DATE 10-6-87

INV. NO. 18379

15-007-21965-0000

CHAPMAN ENERGY, INC.

120 S. MARKET, SUITE 320
 WICHITA, KANSAS 67202
 (316) 262-1191

GEOLOGIST'S REPORT DRILLING TIME AND SAMPLE LOG


OPERATOR Chapman Energy, Inc
 LEASE No. 1 De Geer
 FIELD Deerhead
 LOCATION approx NE NE SE
 SEC. 34 TWSP 32 RNG. 15 w
 COUNTY Barber STATE Kansas

ELEVATIONS
 KB 1994
 DF -
 GL 1981
 MEASUREMENTS ARE ALL
 FROM K.B.

CONTRACTOR Wheatstate
 COMM 11-28-84 COMP. 12-12-84
 RTD 5095 LOG TO 5095
 SAMPLES SAVED FROM 2000 TO TD
 DRILLING TIME KEPT FROM 2000 TO TD
 SAMPLES EXAMINED FROM 2000 TO TD
 GEOLOGICAL SUPERVISION FROM 2250 TO TD
 MUD UP 3710 TYPE MUD Drispac
 GEOLOGIST William G. Hart

CASING RECORD
 SURFACE 13 1/8 @ 295'
 PRODUCTION _____
 ELECTRICAL SURVEYS _____

FORMATION	LOG		SAMPLE		STRUCT COMP.
	TOP	DATUM	TOP	DATUM	
Herington	2343	-349	2341	-347	+8
Topeka	3626	-1632	3628	-1634	+17
Keokuk	4124	-2130	4125	-2131	flat
Brown Lime	4288	-2294	4287	-2293	+1
Lansing	4297	-2303	4295	-2301	-2
Dennis	4615	-2617	4613	-2619	+2
BKC	4758	-2764	4763	-2769	-1
Marmaton	4772	-2778	4774	-2780	+2
Cherokee	4848	-2854	4848	-2854	-1
Mississippian	4860	-2866	4857	-2863	-2
Kinderhook Sh	4885	-2891	4889	-2895	+3
Viola	5025	-3031	5026	-3032	+4



REFERENCE WELL FOR STRUCTURAL COMPARISON

Texas Energies #1-34 UG Geer 2210 FNL BODEWL NELY 34-32-