

1041002

9-26

STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-007-20,939-0000  
260' SW of  
NW SW, SEC. 26, T 32 S, R 15 W/8  
feet from S section line  
feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046  
Operator: Raymond Oil Company, Inc.  
Name & Address: One Main Place, Ste. 900  
Wichita, KS 67202

Lease Name Carr A Well # 1  
County Barber  
Well Total Depth 3650 118.63 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 301

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Gressel Oil Field Service, Inc. License Number 3004  
Address P.O. Box 607, Burrton, KS 67020-0607

Company to plug at: Hour: 3 p.m. Day: 26 Month: 9 Year: 1995  
Plugging proposal received from Art Schoenhofer

(company name) Raymond Oil Company (phone) 316-838-8574

Notes: 4 1/2" at 3648' w/230 sx cement, Perfs at 3563-73'  
1st plug sand back to 3500' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 3:30 p.m. Day: 26 Month: 9 Year: 1995

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3500' and dumped 2 sx cement on top of CIBP,  
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, and 100 sx cement.  
Maximum pressure 400 psi and shut in 100 psi.

RECEIVED

STATE CORPORATION COMMISSION

Remarks: Used 65/35 Pozmix 6% gel by Halliburton. Recovered 2200' of 4 1/2" casing.  
(If additional description is use BACK of this form.)

INVOLVED

observe this plugging.

SEP 28 1995  
9-28-95  
CONSERVATION DIVISION  
Wichita, Kansas  
Stephan J. Griffin  
(TECHNICIAN)

DATE OCT 10 1995

FILE NO. 43712

9-26