

To: 1 041267  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

9-26 API NUMBER 15- 007-21,096-0000  
NW SW NE, SEC. 26, T 32 S, R 15 W/E  
3630 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5046  
Operator: Raymond Oil Company, Inc.  
Name & Address: P.O. Box 48788  
Wichita, KS 67201

Lease Name Mills A Well # 2  
County Barber 119.11  
Well Total Depth 3665 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529  
Address P.O. Box 467, Chase, KS 67524-0209

Company to plug at: Hour: 9:45 a.m. Day: 26 Month: 9 Year: 19 97

Plugging proposal received from Manny Boatwright  
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

were: 4 1/2" at 3663' w/125 sx cement, Perfs at 3573-87, 3587-91'  
1st plug sand back to 3520' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 10:30 a.m. Day: 26 Month: 9 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3456' and dumped 4 sx cement on top of sand bridge through bailer,  
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 100 sx cement.  
Maximum pressure 300 psi and shut in 120 psi.

No wiper plug--cut off braden head and plated w/5 1/2" collar to pump through.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(to be observed) observe this plugging.

DATE 10-2-97  
INV. NO. 49185

Signed Stephen J. Pfeifer (TECHNICIAN)