

1-31

258

061183

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,700-0000
C NE SE, SEC. 26, T 32 S, R 15 W/8
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046
Operator: Raymond Oil Company, Inc.
Name & Address: P.O. Box 48788
Wichita, KS 67201

Lease Name Mills Well # 1 "A"
County Barber 120.25
Well Total Depth 3700 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 24

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:15 a.m. Day: 31 Month: 1 Year: 1989

Plugging proposal received from Mark McCabe

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 3698' PBTB 3670' Perfs at 3584-94'

1st plug sand back to 3530' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 7 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12 p.m. Day: 31 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3530' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 7 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2800' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 2-7-89

INV. NO. 23882

1-31

Signed Paul A. Luthi (TECHNICIAN)