

1030115

807-00495-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NOT AVAILABLE

SE NE, Sec. 16, T 32 S, R 15 W

feet from N/S section line

feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Couldas Well # APO 1

Operator: Phillips Petroleum Company
Name & 7th Floor, Frank Phillips Building
Address Bartlesville, OK 74004

County Barber
Well Total Depth 5099 feet 165.71

BILL TO: Box 287
Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 384

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:00 pm Day: 27 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO James Ray

(company name) Keslo (phone) 316-938-2457

were: 5 1/2 set at 5098 PBD 4667 Perfs 4160-62 Pipe parted 12' below surface
bottom plug pushed plug to 4180' with 10 sx gel, 10# rock, 1 barrel sand and 5 sx
cement.

Top plug squeezed well with 200 sx 60/40 Pozmix 2% gel 3% cc.

Shut-in pressure 200#

Signed Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:50 pm Day: 27 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 5098 PBD 4667 Perfs 4160-62 Pipe parted 12'
below surface. Bottom plug - pushed plug to 4180' with 10 sx gel, 10# rock, 1 barrel
sand and 5 sx cement. Top plug squeezed well with 200 sx 60/40 Pozmix 2% gel 3% cc.

Shut-in pressure 200#.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun Cementing

No recovery

RECEIVED
STATE CORPORATION COMMISSION
FEB 29 1984
2-29-84
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / ~~did not~~) observe this plugging.

Signed Steve Durrant
(TECHNICIAN) ✓

INVOICED
DATE 3/7/84
INV. NO. 0567

FORM CP-2/3
Rev. 9-82