

KCC Per District #4 10-24-13

6 031107

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-24154-00-00

SE NW SE, SEC. 2, T 13 S, R 16 W/E

2920-1650 feet from S section line
4900 1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9008

Lease Name Windholz Well # 1-A

Operator: Sunbelt Pet Inc.
Name & Address: 1033 N Sunny Vale St.
Mesa, Arizona 85201

County Ellis 114.08
Well Total Depth 3510 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number

Address Hays, Ks.

Company to plug at: Hour: AM Day: 21 Month: June Year: 19 88

Plugging proposal received from Issy Kisner

(company name) Sunbelt Pet Inc. (phone)

were: 8 5/8" set at 211 cwc w/140 sks 5 1/2" set at 3509' w/125 sks. Port collar at 1109' cwc w/300 sks. Order 250 sks Cement Blend 5 sks Hulls. B. J. Titan Cement Co.

Darrel's Tank Service

RECEIVED
STATE CORPORATION COMMISSION
10-21-88
OCT 21 1988

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 9:30AM Day: 21 Month: June Year: 19 88

ACTUAL PLUGGING REPORT Test 8 5/8" annulus to 300# psi cement at surface.

Squeezed 5 1/2" casing w/230 sks. w/5 sks Hulls mixed in w/last 100 sks to max psi of 300#.

Close in psi 150#. Plug complete.

Remarks: Any 1100' - 1150' TOC 250 log
(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 10-26-88

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 22733