

14  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 1 1964  
7-1-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Mull Drilling Co., Inc.

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name Heath Well No. # 1

Location C S/2 SE NE Sec. 7 Twp. 32 Rge. 9 (E) (W) W

County Harper Total Depth 4361

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 2:00PM Day 30th Month June Year 1964

The Above well was plugged as follows:

160' of 8 5/8" surface pipe, cemented with 125 sacks. 4361' of 5 1/2" long  
string, cemented with 150 sacks. Plug back to 4556'. Top perferation  
4304'. Bottom of the hole was sanded to 4290', and cemented with 5 sacks.  
Hole was filled with mud to 200', with 10' of rock bridge at 200', and  
cemented with 35 sacks, bringing the top of the cement to 130' in the  
surface pipe. Hole was filled with mud to 40', with 10' of rock bridge,  
and cemented with 10 sacks to base of the cellar.  
3410' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/1/64

INV. NO. 9399-4

Signed: Archie Elving  
Well Plugging Supervisor