

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1965
10-19-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name E. K. Edmiston

Complete Address: 425 First National Bank Bldg., Wichita, Kansas

Lease Name Thomson Well No. # 1

Location C NW SW Sec. 6 Twp. 32 Rge. 9 (E) (W) W

County Harper Total Depth 4425'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Plugging Contractor: E. K. Edmiston Drilling Company

Address: 425 First National Bank Bldg., Wichita, Kans. License No. _____

Operation Completed: Hour 1:00 AM Day 16th Month Oct. Year 1965

The Above well was plugged as follows:

205' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole
was filled with drilling mud to 200', 1st cementing plug, bridged solid
with dry cement and hulls on fluid at 200', and cemented with 25 sacks.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with dry cement and hulls on fluid at 40', and cemented with 10
sacks to the base of the cellar. Rat hole bridged and cemented with 2
sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 10/20/65
INV. NO. 2018-W

Signed: Archie Elving
Well Plugging Supervisor