

15077-00093-00-01

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasRECEIVED  
STATE CORPORATION COMMISSIONMAR 28 1966  
3-28-66  
CONSERVATION DIVISION  
Wichita, KansasOperator's Full Name E. K. EdmistonComplete Address: 501 First National Bank Bldg., Wichita, KansasLease Name Fetrow "B" Well No. # 1Location C SE SW Sec. 6 Twp. 32 Rge. 9 (E) (W)WCounty Harper Total Depth 4453'Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: This hole was a wash downPlugging Contractor: E. K. Edmiston Drilling CompanyAddress: 501 First National Bank Bldg., Wichita, Ks. License No. Operation Completed: Hour 3:00AM Day 26th Month March Year 1966

The Above well was plugged as follows:

700' of 10 3/4" surface pipe, cement circulated. Hole was filled with  
drilling mud to 300', 1st cementing plug, bridged solid with dry cement  
and hulls on fluid at 300', and cemented with 30 sacks. Hole was filled  
with drilling mud to 40', 2nd cementing plug, bridged solid with dry  
cement and 1 sack of hulls on fluid at 40', and cemented with 15 sacks  
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging SupervisorDATE 3/28/66INV. NO. 2949-W