

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1966
7-22-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Aylward Drilling Company

Complete Address: 909 First National Bank Bldg., Wichita, Kansas

Lease Name Skinner "W" Well No. # 1

Location NW NW NE Sec. 10 Twp. 32 Rge. 15 (E) (W) W

County Barber Total Depth 4946'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine Lodge, Kansas License No. 583

Operation Completed: Hour 5:00PM Day 20th Month July Year 1966

The Above well was plugged as follows:

209' of 8 5/8" surface pipe, cemented with 175 sacks. 4928' of 5 1/2" long
string, cemented with 75 sacks. This is an open hole. Bottom of the hole was
sanded to 4910', and cemented with 5 sacks, through the dump bailer. 2500'
of 5 1/2" long string was recovered from the hole. Fluid in the hole was bailed
down to 200', rock bridge and bridge plug from 200' to 190', and cemented with
25 sacks. Hole was filled with mud to 40', rock bridge from 40' to 30', and
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 7/22/66
INV. NO. 3618-W