

W
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1964
9-24-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Messman-Rinehart Oil Company

Complete Address: 1432 Wichita Plaza, Wichita, Kansas

Lease Name Hazelton Land Co. Well No. # 1

Location SE NW Sec. 8 Twp. 32 Rge. 15 (E) (W) W

County Barber Total Depth 4928

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 1:30PM Day 23rd Month Sept. Year 1964

The Above well was plugged as follows:

242' of 10 3/4" surface pipe, cement circulated. 4928' of 5 1/2" long
string, cemented with 100 sacks. Plug back to 4792'. Top perforation
4760'. Bottom of the hole was sanded to 4730', and cemented with 5
sacks. Hole was filled with mud to 240', and 10' of rock bridge, and
cemented with 30 sacks. Hole was filled with mud to 40', and 10' of
rock bridge, and cemented with 15 sacks to the base of the cellar.
2350' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/24/64

INV. NO. 9861-d

Signed: Archie Elving
Well Plugging Supervisor