

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1963

12-9-63

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sinclair Oil & Gas Co.

Complete Address: P. O. Box 521, Tulsa, Oklahoma

Lease Name T. L. Welsh "A" Well No. # 1

Location SE NW SW Sec. 7 Twp. 32 Rge. 15 (E) (W) W

County Barber Total Depth 4985

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 3:00PM Day 5th Month Dec. Year 1963

The Above well was plugged as follows:

311' of 8 5/8" surface pipe, cement circulated. 4895' of 5 1/2" long string,
cemented with 275 sacks. Plug back to 4882'. Top perferation 4811'. Sand-
ed to 4800', bottom cemented with 5 sacks. Fluid level in hole was 275',
plug was set at 275', bridged with 10' of rock, cemented with 25 sacks.
Hole was filled with mud to 40', 10' rock bridge, cemented with 10 sacks
to base cellar.

3168' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICE

Signed: Audie Elving
Well Plugging Supervisor

DATE 12/9/63
INV. NO. 8252-11