

KANSAS
STATE CORPORATION COMMISSION

CPB
OR

WELL PLUGGING SUPERVISOR'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 72-28 Location: SE NE NE
County: Barber Sec. 13 Twp. 32 Rge. 15 (E) (W) X
Name of Field or Pool: _____ Total Depth: 4818

I have this date completed supervision of plugging of:

Well No. 1 Lease Stump Smith "E"

RECEIVED
STATE CORPORATION COMMISSION

Operator's Full Name National Cooperative Refinery Ass'n.

FEB 17 1958
2-17-58
CORPORATION DIVISION
Wichita, Kansas

Complete Address: 305 Rule Building, Wichita, Kans.

Plugging Contractor: Ace Pipe Pulling Co.

Address: Great Bend, Kansas License No. 2

Abandoned Oil Well _____ Gas Well _____ X Input Well _____ SWD Well _____ D & A _____

If well is a rotary drilled dry hole did operators wait for you to arrive _____

If yes how long _____ Reason: _____

Operation Completed: Hour 11 A.M. Day 13 Month February Year 1958

The above well was plugged as follows:

185 feet of 8 5/8" casing was circulated with 185 sacks of cement.
Perf. 4725 to 4736. Sand to 4710 with five sack cement dumped on
sand with dump bailer. Pipe shot off and pulled to 1700 and hole
circulated with heavy jell mud by Globe Cementing Co. Mud to 300'
with rock bridge at 300' with 20 sack cement on top of plug or bridge.
Mud to 35 feet. Rock bridge at 35' with 10 sack cement to surface.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: *[Signature]*
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Reviewed: *[Signature]*
Field Supervisor

Signed: _____
Well Plugging Supervisor

PLUGGING
FIL SEC 13 T. 32 R. 15 W
BOOK PAGE 72 LINE 28