

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC - 6 1965
12-6-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name National Cooperative Refinery Assoc.

Complete Address: P. O. Box 6, Great Bend, Kansas

Lease Name Stumph-Smith "E" Well No. # 2

Location C S/2 SE NE Sec. 13 Twp. 32 Rge. 15 (E) (W) W

County Barber Total Depth 4845'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 9:30 AM Day 1st Month Dec. Year 1965

The Above well was plugged as follows:

225' of 8 5/8" surface pipe, cemented with 200 sacks. 4845' of 5 1/2" long
string, cemented with 155 sacks. Plug back to 4820'. Top perferation 4746'.
Bottom of the hole was sanded to 4700', and cemented with 5 sacks. 3610'
of 5 1/2" long string was recovered from the hole. Hole was filled with mud
to 230', rock bridge from 230' to 220', and cemented with 25 sacks. Hole
was filled with mud to 40', rock bridge from 40' to 30', and cemented
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/7/65
INV. NO. 2344-W

Signed: Archie Elving
Well Plugging Supervisor