

9

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
10-15-71  
OCT 13 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Champlin Petroleum Co.

Complete Address Box 308 Ellinwood, Ks

Lease Name Baird Well No. 1

Location SE/NE/SW Sec. 22 Twp. 32 Rge. 15 (E) (W) W

County Barber Total Depth 5324

Abandoned Oil Well        Gas Well        Input Well        SWD Well X D & A       

Other well as hereafter indicated       

Plugging Contractor Glenn & Smith Pipe Pulling Co.

Address 204 E 6th Ellinwood, Ks License No. 396

Operation Completed: Hour 11:00 AM Day 12 Month 10 Year 1971

The above well was plugged as follows:

473 ft 10 3/4 surface pipe cemented with 275 sacks. 5279 ft 4 1/2 long  
string cemented with 900 sacks. Top perf. 4987 ft. Set plug at  
4900 ft, 4 sacks cement with bailer. Pulled 800 ft 4 1/2. Set 20 ft  
rock bridge at 250 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. Russell B. Bunting  
Well Plugging Supervisor

DATE 10-12-71  
INV. NO. 4474-11/2