

9
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1966
10-24-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sinclair Oil & Gas Company Oklahoma City
Complete Address: 580 Executive Terrace Bldg., 2809 NW expressway, Oklahoma

Lease Name T. L. Welsh "D" Well No. # 1

Location SW NE SE Sec. 18 Twp. 32 Rge. 15 (E) W

County Barber Total Depth 4914'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine Lodge, Kansas License No. 583

Operation Completed: Hour 1:45PM Day 22nd Month Oct. Year 1966

The Above well was plugged as follows:

320' of 10 3/4" surface pipe, cemented with 250 sacks. 4908' of 4 1/2"
long string, cemented with 225 sacks. Plug abck T.D. 4848'. Top perferation
4725'. Bottom of the hole was sanded to 4700', and cemented with 3 sacks,
through the dump bailer. 3800' of 4 1/2" long string was recovered from the
hole. Fluid in the hole was bailed down to 275', bridge plug and rock bridge
from 275' to 265', and cemented with 30 sacks. Hole was filled with mud
to 40', rock bridge from 40' to 30', and cemented with 15 sacks to the
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 10/24/66
INV. NO. 4169-w

Signed: Archie Elving
Well Plugging Supervisor