

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23414-00-00
Spot: SEWSE Sec/Twnshp/Rge: 28-25S-5E
1780 feet from S Section Line, 1820 feet from E Section Line
Lease/Unit Name: HEGBERG A Well Number: 199
County: BUTLER Total Vertical Depth: 2536 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 236 200 SX CMT
Production: Size 5.5 feet: 2450 365 SX CMT
Liner: Size feet:

82.42

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/14/2001 12:00 PM
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORP. Phone: (316) 832-1537

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DONALD HOBERECHT Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/14/2001 2:30 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Set cast iron bridge plug at 1900'. Perf casing at 520'. Circulated cement from 520' to surface w/100sxs 60/40 poz w/ 4% gel. 900# max P.S.I 500# shut in psi.

RECEIVED
KCC DISTRICT #2

MAR 21 2001

WICHITA, KS

INDEXED


03-23-2001
2001061534

Remarks: UNITED #2505

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)