

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07266-00-00
Spot: SESENE Sec/Twnshp/Rge: 36-18S-11W
2951 feet from S Section Line, 295 feet from E Section Line
Lease Name: MUSENBERG Well #: 1
County: BARTON Total Vertical Depth: 3306 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5	3304		
SURF	8.625	150		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2013 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ED SCHUMACHER Company: KCC Phone: (785) 625-0550

Proposed Plugging Method:	Ordered 750 sx 60/40 pozmix 4% gel cement, 11 sx gel and 800 # hulls. Control # 20130071-001 Dig Safe # 1339506
---------------------------	---

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/20/2013 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Well bridged at 11 joints, 15 joints and 16 joints down. Drilled through bridges with pump and swivel. Perforated through tubing at 1350', 520' and 200'. Ran tubing to 2950' and pumped 11 sx gel followed by 50 sx cement and 200 # hulls. Pulled tubing to 700' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 200'. Circulated cement to surface on casing with 100 sx cement. Cut off casing and surface pipe 15' down and ran 1" pipe down casing. Circulated cement to surface with 20 sx cement. Ran 1" pipe down surface pipe and circulated cement to surface with 30 sx cement.

GPS: 38.44279 -098.48164

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 15 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY WELL SERVICE TICKET # 5866 FEE FUND PROJECT MUSENBERG "MARY IDA" CONTROL # 20130071-001

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

OCT 07 2013