

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-19111-00-01  
Spot: SWSENE Sec/Twnshp/Rge: 36-18S-11W  
2952 feet from S Section Line, 951 feet from E Section Line  
Lease Name: MARY IDA Well #: 10  
County: BARTON Total Vertical Depth: 3309 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5	3288		
SURF	8.625	205		

Well Type: EOR UIC Docket No: E29031.1 Date/Time to Plug: 09/24/2013 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ED SCHUMACHER Company: KANSAS CORP. COMM. Phone: (785) 625-0550

Proposed  
Plugging  
Method: Ordered 750 sx 60/40 pozmix 4% gel cement, 14 sx gel and 800 # hulls.  
Control # 20130071-003  
Dig Safe # 1339506

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/24/2013 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350', 520' and 200'.  
Ran tubing to 2950' and pumped 14 sx gel followed with 50 sx cement and 200 # hulls. Pulled tubing to 1380' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 700'. Circulated cement to surface on casing with 90 sx cement and 250 # hulls. Pulled tubing. Tied to casing and topped off w/25 sx cement. Shut in pressure 600 psi. Cut off casing and surface pipe and topped off with 30 sx cement on casing and surface pipe.

GPS: 38.44281 -098.48393

Perfs:

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 15 2013

CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY WELL SERVICE TICKET # 5973 FEE FUND PROJECT MUSENBERG "MARY IDA" CONTROL # 20130071-003

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

*cc to UIC 10/17/13*

*PM*

OCT 07 2013