

1-19

2-040793
RECEIVED
KANSAS CORPORATION COMMISSION

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 207B
Wichita, Kansas 67202

MAR 09 1995
3-9-95
CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-077-20,796-0000
C SE NW, SECTION 24 TOWNSHIP 32 RANGE 9W

OPERATOR LICENSE # 5039 3300 FEET FROM S SECTION LINE
3300 FEET FROM E SECTION LINE

OPERATOR ATTICA GAS VENTURES CORP
NAME & 123 MAIN
ADDRESS ATTICA KS 67009

LEASE NAME: DOLL #1 ^{121.84}
COUNTY: HARPER
WELL TOTAL DEPTH: 3749' ^{PB 3600'}

PIPE: 4-1/2" @ 3737'

SURFACE CASING: 8-5/8 @ 305'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: CLARKE CORP
ADDRESS: MEDICINE LODGE KS LICENSE: 5105

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: ALAN
COMPANY NAME: CLARK CORP PHONE: 316-

WERE: CIBP 3600' - PERFS 3482'-3490' - SAND TO 3430' & 4 SX
- 35 SX @ 1350' - 35 SX @ 850' - CIRC 355' TO 0'

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 1530 DAY: 19 MONTH: 1 YEAR: 1995

ACTUAL PLUGGING REPORT:
PERFS COVERED W/SAND FROM 3600-3300' & CAPPED W/4 SX
CMT - 4-1/2" CSG REC FROM 2950' - 35 SX CMT PLUGS SPTD
THRU 4-1/2" @ 1355' & 820' - CMT CIRC FROM 360' - 0'
THRU 4-1/2" CSG - REMAINING 4-1/2" PULLED & TOPPED OFF
W/CMT

REMARKS: ALLIED CMT 60/40 4%

INVOICED
DID OBSERVE THIS PLUGGING.
DATE: 3-10-95
INV. NO. 42345


Steve Van Gieson (AGENT)