

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

12-17

20875-0000

API NUMBER: 15-077-20,815

140' E SW NE, SECTION 24 TOWNSHIP 32 RANGE 9W

OPERATOR LICENSE # 5039 3300 FEET FROM S SECTION LINE  
OPERATOR ATTICA GAS VENTURES CORP. 1840 FEET FROM E SECTION LINE  
NAME & 123 NORTH MAIN  
ADDRESS ATTICA, KS 67009  
LEASE NAME: FERRELL #3 121.29  
COUNTY: HARPER  
WELL TOTAL DEPTH: 3732' PB 3560'  
PIPE: \_\_\_\_\_  
SURFACE CASING: 8 5/8" @ 259'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL X INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: CLARKE CORPORATION  
ADDRESS: P.O. BOX 187, MEDICINE LODGE, KS 67104 LICENSE: 5105

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: ALAN VRATEL  
COMPANY NAME: CLARKE CORPORATION PHONE: (316) 886-5665  
WERE: SAND TO 3400' AND 4 SACKS OF CEMENT PERFS 3461-51'  
35 SACKS AT 1350-71'  
35 SACKS AT 861'  
CIRCULATE CEMENT TO SURFACE FROM 310'

PLUGGING PROPOSAL RECEIVED BY: SVG

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( ) PART ( X ) NONE ( )

COMPLETED: HOUR: \_\_\_\_\_ DAY: 17 MONTH: 12 YEAR: 1996

ACTUAL PLUGGING REPORT: THE PERFS WERE COVERED WITH SAND FROM 3732' TO 3400' AND CAPPED WITH 4 SACKS OF CEMENT. THE PIPE WAS RECOVERED FROM 2800' AND PULLED FROM THE WELLBORE. TUBING WAS RUN TO 1371' WHERE 35 SACKS OF CEMENT WAS SPOTTED. THE TUBING WAS PULLED TO 861' WHERE 35 SACKS OF CEMENT WAS SPOTTED. THE TUBING WAS PULLED TO 317' WHERE CEMENT WAS CIRCULATED TO SURFACE.

REMARKS: 60/40 POZ 4% GEL

INVOICED

RECEIVED  
KANSAS CORPORATION COMMISSION

I DID OBSERVE THIS PLUGGING.

DATE DEC 31 1996  
MIS NO 47194

DEC 30 1996  
12-30-96  
CONSERVATION DIVISION  
WICHITA, KS

Steve Van Gieson  
STEVE VAN GIESON