

2-1

2-040796

RECEIVED
KANSAS CORPORATION COMMISSION

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

MAR 09 1995
3-9-95
CONSERVATION DIVISION
WICHITA, KS
E-25, 02

API NUMBER: 15-077-20,950

100' N SW SW SW, SECTION 21 TOWNSHIP 32 RANGE 9W

OPERATOR LICENSE # 5039 430 FEET FROM S SECTION LINE
4950 FEET FROM E SECTION LINE

OPERATOR ATTICA GAS VENTURES
NAME & 123 MAIN
ADDRESS ATTICA KS 67009

LEASE NAME: JOHNSTON #2
COUNTY: HARPER 143.65
WELL TOTAL DEPTH: 4420' PB 4382'
PIPE: 4-1/2" @ 4419'

SURFACE CASING: 8-5/8" @ 259'

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: CLARKE CORPORATION
ADDRESS: MEDICINE LODGE KS LICENSE: 5105

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: ALAN VRATEL

COMPANY NAME: CLARKE CORPORATION PHONE: 316-

WERE: SAND TO 4300' & 4 SX - RECOVER 3700' - 35 SX @
1329' - 35 SX @ 802' - CIRC 311' TO SURF - PBSD 4382' -
PERF 4348-54'

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 13:30 DAY: 1 MONTH: 2 YEAR: 1995

ACTUAL PLUGGING REPORT:
PERFS WERE COVERED W/SAND TO 4300' & CAPPED W/4 SX
CMT - 4-1/2" RECOVERED FROM 3700' & PULLED TO 1329' &
35 SX CMT SPOTTED - 4-1/2" PULLED TO 805' & 35 SX CMT
SPOTTED - 4-1/2" PULLED TO 311' & CMT CIRC TO SURF -
4-1/2" PULLED OUT & CMT TOPPED OFF

REMARKS: ALLIED 60/40 4% GEL

I DID OBSERVE THIS PLUGGING.

INVOICED

Steve Van Gieson
Steve Van Gieson (AGENT)

DATE 3-10-95
INV. NO. 4-2348

FORM CP-2/3
REV. 3/90