

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-30260-00-01  
Spot: W2SWNW Sec/Twnshp/Rge: 35-18S-21W  
1980 feet from N Section Line, 510 feet from W Section Line  
Lease/Unit Name: MELLICK OWWO Well Number: A-1  
County: NESS Total Vertical Depth: 4300 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

Production Casing Size: 4.5 feet: 4295 WITH 75 SX CMT  
Surface Casing Size: 8.625 feet: 246 WITH 175 SX CMT

*\$139<sup>75</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/22/2003 10:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (620) 275-7461

Proposed Plugging Method: PUMP 200# HULLS & 20 SX CMT. PEFORATE 4 1/2". PUMP CMT & HULLS. PRESSURE TEST. CHECK BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/22/2003 5:14 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:


PBTD 4529'. PERFS AT 4209-4214'. PUMP DOWN 4 1/2" WITH 200# HULLS & 20 SX CMT. 61 BBL DISPLACEMENT. MAXIMUM PRESSURE 1100 PSIG. SHUT IN PRESSURE 800 PSIG. PERFORATED 4 1/2" AT 650'. PUMPED DOWN 4 1/2" WITH 80 SX CMT- 200# HULLS - 40 SX CMT. MAXIMUM PRESSURE 600 PSIG. SHUT IN PRESSURE 400 PSIG. PRESSURED UP 8 5/8" X 4 1/2" ANNULUS WITH 40 SX CMT. MAXIMUM PRESSURE 400 PSIG. BLEW HOLE IN 8 5/8".

RECEIVED  
10-28-03  
OCT 28 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

*Richard W. Lacey*  
INVOICE (TECHNICIAN)  
10-28-03  
WV. CO. 2004060687

Form CP-20

