

KANSAS

Form CP-3

Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
 Administrator
 P. O. Box 17027
 Wichita, Kansas 67217

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 4 1973
 1-4-73
 CONSERVATION DIVISION
 Wichita, Kansas

Operator's Full Name Walters Drlg. Co.
 Complete Address 400 Insurance Bldg Wichita, KS
 Lease Name Skinner Y Well No. 2
 Location SW/SW/NE Sec. 11 Twp. 32 Rge. 15 (E) (W) W
 County Barber Total Depth 5311
 Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D & A _____
 Other well as hereafter indicated _____
 Plugging Contractor Russ Casing Pulling Co. Inc
 Address Box 1182 Great Bend, KS License No. 623
 Operation Completed: Hour 11:00 AM Day 2 Month 1 Year 1973

The above well was plugged as follows:

317 ft 8 5/8 surface pipe cement circulated. 5205 ft 5 1/2 long string
 cemented with 75 sacks. Top perf. 5189 ft. Sand to 4300 ft, 5 sacks
 cement with bailer. Pulled 800 ft 5 1/2. Set 10 ft rock bridge at
 360 ft. Fill hole with 6 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
 Well Plugging Supervisor

DATE 1/4/73INV. NO. 6810-W