

15-007-30041-0000

Form CP-3
Rev. 6-4-68

KANSAS

sl
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 30 1972
S-30-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Ferguson Oil Co. Inc.

Complete Address 2700 Liberty Tower Oklahoma City, OK

Lease Name Skinner Well No. B-1

Location C SE/SW Sec. 11 Twp. 32 Rge. 15 (E) (W)

County Barber Total Depth 5067

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Clarks Oilfield Service

Address 107 W Fowler Medicine Lodge, Ks License No. 583

Operation Completed: Hour 9:30 AM Day 27 Month 5 Year 1972

The above well was plugged as follows:

217 ft 8 5/8 surface pipe cemented with 200 sacks. 5050 ft 5 1/2 long
string cemented with 200 sacks. Top perf. 4950 ft. Sand back to
4927 ft, 5 sacks cement with bailer. Pulled 4160 ft 5 1/2. Set 20 ft
rock bridge at 200 ft. Fill hole with 3 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *L. Russell B. Hunter*
Well Plugging Supervisor

INVOICED

DATE 5/31/72
INV. NO. 5784-W