

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority  
Issued, December 22, 1966  
CONSERVATION DIVISION  
Wichita, Kansas

JAN 17 1967

1-17-67

Operator's Full Name National Cooperative Refinery Assoc.

Complete Address: P. O. Box 6, Great Bend, Kansas

Lease Name Stumph-Smith "D" Well No. # 1

Location SE SE NE Sec. 12 Twp. 32 Rge. 15 (E) (W) W

County Barber Total Depth 4965'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Ralph Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 3:30PM Day 16th Month Jan. Year 1967

The Above well was plugged as follows:

241' of 8 5/8" surface pipe, cemented with 200 sacks. 4959' of 5 1/2" long  
string, cemented with 75 sacks. Plug back T. D. 4963'. This is an open  
hole. Bottom of the hole was sanded to 4950', and cemented with 5 sacks,  
through the dump bailer. 3817' of 5 1/2" long string was recovered from the  
hole. Fluid in the hole was bailed down to 235', bridge plug and rock  
bridge from 235' to 225', and hole was filled with 3 1/2 yards of ready-  
mix cement, from 225' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Arlie Elving  
Well Plugging Supervisor

DATE 1/17/67  
INV. NO. 4619-u