

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION

SEP 24 1964

CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Colorado Oil & Gas CorporationComplete Address: Box 1030, Wichita, KansasLease Name Kennedy Well No. # 1Location SE SE SE Sec. 2 Twp. 32 Rge. 13 (E) (W) WCounty Barber Total Depth 4575Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: This hole was a wash downPlugging Contractor: Forbes Casing Pulling Inc.Address: Box 221, Great Bend, Kansas License No. 49Operation Completed: Hour 2:00PM Day 22nd Month Sept. Year 1964

The Above well was plugged as follows:

599' of 10 3/4" surface pipe, cement circulated. 4400' of 4 1/2" long
string, cemented with 150 sacks. Plug back to 4100'. Top perforation
4002'. Bottom of the hole was sanded to 3990', and cemented with 3
sacks. Fluid level in the hole was at 300'. Bridge plug was set on
fluid at 300', and 10' of rock bridge, and cemented with 30 sacks.
Hole was filled with mud to 40', and 10' of rock bridge, and cemented
with 15 sacks to the base of the cellar.

3588' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

DATE 9/24/64INV. NO. 9859-WSigned: Archie Elving
Well Plugging Supervisor