

R

Form CP-3
Rev. 6-9-67

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed August 8, 1967.

RECEIVED
STATE CORPORATION COMMISSION
AUG 21 1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address 300 West Douglas. Wichita, Kansas 67202

Lease Name Gant "B" Well No. # 1

Location C NE NE Sec. 8 Twp. 32 Rge. 13 (E) (W) W

County Barber Total Depth 4400'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor S & S Drilling Company

Address Box 645, Great Bend, Kansas 67530 License No.

Operation Completed: Hour 3:30 P.M. Day 19th Month August Year 1967

The above well was plugged as follows:

259' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole was
filled with drilling mud to 250', 1st cementing plug, bridged with 2 sacks
of dry cement and 1/2 sack of hulls on fluid at 250', and cemented with 23
sacks, with cement from 250' to 175'. Hole was filled with drilling mud
to 40', 2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack
of hulls on fluid at 40', and cemented with 9 sacks, with cement from 30'
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8-22-67
INV. NO. 6170-W