



15:35:01012-0000

GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date Oct 21, 19 60, authorized the following plugging operation:

Operator's Full Name: R. N. Shields
 Complete Address: 308 Rule Bed - Wichita, Kans
 Lease Name: ~~RYERSEE~~ RYERSEE Well No. 121
 Location: NW/4 Sec. 35 Twp. 18 Rge. 21 (E) (W)
 County: Ness Total Depth: 4233
 Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

Jet Pitts circulate hole with heavy mud, set cementing plug at 600ft. and displace 20 sax cement thru drill pipe, heavy mud to 293ft, set cementing plug and displace 20 sax cement, heavy mud to 40' set and tie cementing plug in place with wire and dump 1/2 sax dry bulls and 10 sac cement, cementing to base of cellar.

RECEIVED
 STATE CORPORATION COMMISSION
 11-16-60
 NOV 16 1960
 CONSERVATION DIVISION

Very truly yours,
 Gilbert P. Leiker
 Signed: Gilbert P. Leiker
 Conservation Division Agent