

15-135-80067-0000

cl 3

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
10-23-61
OCT 23 1961

CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ness

Location: SE NE SW Sec. 35 Twp. 18 Rge. _____ (E) _____ (W) 21

Name of Field: Lank Total Depth: 4255'

I have this date completed supervision of plugging of:

Lease Name: Lank Well No. 1

Operator's Full Name: Stickel Dng Co

Complete Address: 1100 Bitting Bldg Wichita, Kansas

Plugging Contractor Knight Casing Pulling

Address: Chase, Kansas License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated; _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 10AM Day 19 Month 10 Year 61

The above well was plugged as follows:

8 5/8" 290' circulated with cement - 5 1/2" 4253' with 100 sax cement -
PB to 4196' - perf 4170'
Filled with sand to 4150', set 4 sax cement with dump bailer
Pulled 3441' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" at
550', (20 sax Gel), displaced 20 sax cement through 5 1/2" at 550', heavy
mud to 170', displaced 20 sax cement through 5 1/2" at 170', heavy mud to
35', set bridge and filled to bottom cellar with cement.

Mudding and cementing by Knight Casing Pulling pump truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 10/30/61
INV. NO. 3911-W