

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued June 21, 1967.

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1967
6-26-67
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name John O. Farmer, Inc.
Complete Address 370 W. Wichita, Russell, Kansas 67665
Lease Name Werner "B" Well No. # 2
Location C N/2 SW NW Sec. 18 Twp. 32 Rge. 9 (E) (W)W
County Harper Total Depth 4344'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Knight Casing Pulling Company
Address Box 405, Chase, Kansas License No. 436
Operation Completed: Hour 2:00 P.M. Day 21st Month June Year 1967

The above well was plugged as follows:

255' of 8 5/8" surface pipe, cement circulated. 4344' of 5 1/2" long string,
cemented with 75 sacks. Top perforation 4336'. Bottom of the hole was
sanded to 4300', and cemented with 5 sacks, through the dump bailer. 3802'
of 5 1/2" long string was recovered from the hole. Hole was filled with mud
to 250', rock bridge from 250' to 240', and cemented with 25 sacks. Hole
was filled with mud to 40', rock bridge from 40' to 30', and cemented
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/26/67
INV. NO. 5452-W

Signed: Archie Elving
Well Plugging Supervisor