

KANSAS

KP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUL 1 1966
7-1-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Frank J. Black

Complete Address: Box 150, McPherson, Kansas

Lease Name Werner "A" Well No. # 2

Location NW NW NW Sec. 18 Twp. 32 Rge. 9 (E) W

County Harper Total Depth 4346'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 6:30PM Day 29th Month June Year 1966

The Above well was plugged as follows:

253' of 8 5/8" surface pipe, cement circulated. 4341' of 5 1/2" long
string, cemented with 100 sacks. This is an open hole. Bottom of the
hole was sanded to 4325', and cemented with 5 sacks, through the dump
bailer. 3717' of 5 1/2" long string was recovered from the hole. Hole
was filled with mud to 250', rock bridge from 250' to 240', and cement-
ed with 25 sacks. Hole was filled with mud to 40', rock bridge from
40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/1/66
INV. NO. 3492-U