

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 30 1964
7-30-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name Black "A" Well No. # 1

Location C SW NE Sec. 14 Twp. 32 Rge. 9 (E) (W) W

County Harper Total Depth 4507

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sargent Casing Pulling Service

Address: 121 West 9th, Liberal, Kansas License No. 511

Operation Completed: Hour 10:30AM Day 29th Month July Year 1964

The Above well was plugged as follows:

37' of 13 3/8" conductor pipe, cement circulated. 314' of 8 5/8" surface
pipe, cemented with 225 sacks. 4506' of 4 1/2" long string, cemented with
100 sacks. Plug back to 4390'. Top perforation 4409'. Bottom of hole was
chatted to 4400', cast iron plug set at 4400', and cemented with 5 sacks.
Hole was filled with mud to 275', and 10' of rock bridge, cemented with
35 sacks. Hole was filled with mud to 40', and 10' of rock bridge, cement-
with 10 sacks to base of the cellar.

4016' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/30/64

INV. NO. 9562-W

Signed: Archie Elving
Well Plugging Supervisor