

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 23 1966
11-23-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Weathered Well No. # 1

Location C W/2 SW SW Sec. 4 Twp. 32 Rge. 9 (E) (W)

County Harper Total Depth 4410'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: P. O. Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 5:30PM Day 22nd Month Nov. Year 1966

The Above well was plugged as follows:

160' of 8 5/8" surface pipe, cemented with 135 sacks. 4403' of 5 1/2" long
string, cemented with 75 sacks. Plug back T.D. 4365'. Top perferation
4296'. Bottom of the hole was sanded to 4275', and cemented with 5 sacks,
through the dump bailer. 3727' of 5 1/2" long string was recovered from the
hole. Hole was filled with mud to 180', rock bridge from 180' to 170',
and cemented with 25 sacks. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/29/66

INV. NO. 4335-W

Signed: Archie Elving
Well Plugging Supervisor