

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

NOV 21 1966
11-21-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Simpson Well No. # 1

Location C SW NE Sec. 4 Twp. 32 Rge. 9 (E) (W) W

County Harper Total Depth 4455'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: P. O. Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 11:45AM Day 18th Month Nov. Year 1966

The Above well was plugged as follows:

200' of 8 5/8" surface pipe, cemented with 100 sacks. 4454' of 4 1/2" long
string, cemented with 110 sacks. Plug back T.D. 4418'. Top perferation
4346'. Bottom of the hole was sanded to 4325', and cemented with 3 sacks,
through the dump bailer. 3785' of 4 1/2" long string was recovered from
the hole. Hole was filled with mud to 200', rock bridge from 200' to
190', and cemented with 25 sacks. Hole was filled with mud to 40',
rock bridge from 40' to 30', and cemented with 10 sacks to the base of
the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 11/21/66
INV. NO. 4309-W