



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1974
6-18-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Crowe of DaMac Drig Co Inc has this

date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: SeRoBee & Shaffer

Complete Address: 401 Wolcott Bldg Hutchinson, KS

Lease Name: Clark Well No. 1

Location: C NE/SW Sec. 18 Twp. 32s Rge. 9 (E)(W) W

County: Harper Total Depth 4337 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Crowe was instructed to plug the well as follows:

250 ft 8 5/8 surface cemented with 200 sacks. Pump plug,

35 sacks cement to 250 ft. Mud to 40 ft, plug, 1/2 sack

hulls, 10 sacks cement to surface. 2 sacks cement in rat

hole, 2 Sacks cement in mouse hole.

Pumped by Allied Cementing Co Great Bend, KS

Very truly yours,

Russell Christman
Conservation Division Agent