

State of Kansas

FORM - CP-2
Rev. 6-26-62



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 3 1963
7-3-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Frank Pfannenstiel of Garvey Drilling Co. has this date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: De Geer Well No. # 1

Location: NE SE Sec. 35 Twp. 32 Rge. 15 (E) (W) W

County Barber Total Depth 5230 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pfannenstiel was instructed to plug the well as follows:

276' of 13 3/8" surface pipe, cement circulated with 250
sacks. Fill hole with mud to 240', 1st cementing plug,
1/2 sack hulls, cement with 30 sacks. Fill hole with mud to
40', 2nd cementing plug, 1/2 sack hulls, cement with 20
sacks to base cellar. Bridge and cement rat hole with 2
sacks.

Very truly yours,

Archie Elving
Conservation Division Agent