

State of Kansas



JOHN ANDERSON, Jr. Governor  
 WILLIAM L. MITCHELL Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY O. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 9 1965  
 7-9-65  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita 2, Kansas

Dear Sir:

Mr. Tuney Burger of Sunray DX Oil Company has this date requested permission to plug the following described well:

Mr. Burger guarantees payment of the plugging fee.

Operator's full Name: Sunray DX Oil Company

Complete Address: 300 Union National Bldg., Wichita, Kans.

Lease Name: Vaughn Degeer Well No. # 1

Location: SW NW NE Sec. 32 Twp. 32 Rge. 15 (E) (W) W

County Barber Total Depth 5425' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Burger was instructed to plug the well as follows:

225' of 13 3/8" surface pipe, cement circulated with 275 sacks.  
Fill hole with drilling mud to 225, 1st cementing plug, bridge  
with hulls, and cement with 50 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cement  
with 20 sacks to base cellar. Bridge and cement rat hole with  
2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent