

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

APR 8 1963

CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Hopkins of Aylward Drilling Co. has this

date requested permission to plug the following described well:

Mr. Hopkins guarantees payment of the plugging fee.

Operator's full Name: Aylward Drilling Co.

Complete Address: 813 1st National Bank Bldg., Wichita, Kans.

Lease Name: Lenkner Well No. # 1

Location: C NW NW Sec. 15 Twp. 32 Rge. 13 (E) (W) W

County Barber Total Depth 4515 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hopkins was instructed to plug the well as follows:

208' of 8 5/8" surface pipe, circulated with 250 sacks cement.
Fill hole with mud to 180', 1st cementing plug, 1/2 sack hulls,
cement with 20 sacks. Fill hole to 40' with mud, 2nd cementing
plug, 1/2 sack hulls, Cement with 10 sacks to base cellar.
Cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent