

STATE OF KANSAS
STATE CONSERVATION DIVISION
CONSERVATION DIVISION
130 S. MARKET, ROOM 2078
Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 7 2001

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM AND FILE ONE COPY)

API # 15-015-21,344 · 00 · 00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

CONSERVATION DIVISION

WELL OPERATOR VESS OIL CORPORATION KCC LICENSE # 5030
(owner/company name) (operator's)
ADDRESS 8100 E. 22nd St. North, Bldg. 300 CITY Wichita
STATE Kansas ZIP CODE 67226 CONTACT PHONE # (316) 682-1537
LEASE Stokes A WELL# 123 SEC. 33 T. 25S R. 05E (East/West)
NE SW NW SPOT LOCATION/QQQQ COUNTY Butler

6/01

2640 FEET (in exact footage) FROM S (circle one) LINE OF SECTION (NOT Lease Line)
660 FEET (in exact footage) FROM E (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL _____ D&A _____ SWD/ENHR WELL _____ DOCKET # _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8-5/8" SET AT 237' CEMENTED WITH _____ 175 SACKS
PRODUCTION CASING SIZE 4-1/2" SET AT 2149' CEMENTED WITH _____ 200 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 1945-49'; 1954-58'; 2048-55; 2068-72

ELEVATION 1374/1377 T.D. 2150' PBDT 2129' ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Spot 50 sx Class A, plug @ 1945', tag with wireline. Perf 4 shots at 287'
Circ. 100 sx 60/40 Pozmix, 4% gel down casing and up backside until full.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? YES

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Casey Coats PHONE (316) 682-1537

ADDRESS 8100 E. 22nd Street North, Bldg. 300 CITY/STATE Wichita, KS 67226

PLUGGING CONTRACTOR United Acid & Cementing KCC LICENS 31529
(contractor's)

ADDRESS P.O. Box 712, El Dorado, KS 67042 PHONE # (316) 321-4680

PROPOSED DATE AND HOUR OF PLUGGING (If known?) finish 5/7/01 - 8:00 a.m. plugged

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 05/04/2001 AUTHORIZED OPERATOR/AGENT: Casey Coats
(signature)

AK