

RECEIVED

1 AUG 30 2001

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 SOUTH MARKET - ROOM #2078
WICHITA, KANSAS 67202-3802

Form CP-1 (3/92)

15-015-19080-00-00
KCC WICHITA Well Plugging Application Form - File One Copy

API# 3/44

List for well drilled since 1967, if no API# was issued, use spud or completion.

Well Operator: Petroleum Property Services Inc. KCC License # 31142 ^{1/02}
 Address: 155 North Market #1010, Wichita, KS 67202-1824 Phone: 316-265-3351
 Lease: JACKSON Well: 1 SEC:24 TWN:25S RANGE: 4E
 Spot Location: NE NE SE County: BUTLER
 2310 Feet from SOUTH Line of Section Docket
 330 Feet from EAST Line of Section Number
 Oil Well: X Gas Well: D&A: SWD/EHNR:
 Conductor Casing Size: Set At: Cemented With: Sacks
 Surface Casing Size: Set At: Cemented With: Sacks
 Production Casing Size: 7" Set At: 2515 Cemented With: NA Sacks
 List Perforations & Bridge Plugs: 4 1/2, 9.5# LINER SET @ 2530 WITH 250 SX, OPEN HOLE
 2530-71, PERFORATIONS 2513-22
 Elevation: NA (G.L./K.B.) T.D.: 2571 PBD: Anhydrite Depth:
 (Stone Corral Formation)
 Condition of Well: Good: Poor: Csg Leak: X Junk:

Proposed Method of Plugging: ACCORDING TO KCC INSTRUCTIONS

Is Well Log Attached To This Application As Required? YES Is ACO-1 Filed? NO
If Not Explain Why? DRILLED PRIOR TO ACO-1

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

List Name Of Company Representative Authorized To Be In Charge Of Plugging Operations:

LARRY WALLERT
Mobile Phone: 785-483-1558

Address: P.O. Box 551, Russell, KS 67665 Phone: 785-483-2022


Plugging Contractor: PETROLEUM PROPERTY SERVICES INC. KCC License #: 31142 ^{1/02}
Address: 155 NORTH MARKET #1010, WICHITA, KS 67202 Phone: 316-265-3351

Proposed Date & Hour of Plugging (If Known):

Payment Of The Plugging Fee (K.A.R. 82-3-118) Will Be Guaranteed By Operator Or Agent.

Date: 8/28/2001

Authorized Operator/Agent:


JIM THATCHER

STATEMENT

AP 72

ELMORE'S, INC.
Box 277 - 419 S. Montgomery
Sedan, KS 67361
(620) 725-5744
Eve. 725-5538

Date 8-21-01

Customer Pigdon + Bruen
Address _____
City _____ State _____ Zip _____

Qty.	Description	Price	Amount
174	SKS Cement	7.00	1218.00
5	hr Cement Pump	50.00	250.00
2	SKS Coel	11.00	22.00
5	hr Water Truck	50.00	250.00
1	Bank Tank	50.00	50.00
1	Perforation	200.00	200.00
	Grilled Casing At 950	\$	1990.00
	Pumped 20 Sk Cement	Tax	127.36
	Plus 1" 6 1/4 Casing	\$	2117.36
	Pulled 1" Out Perforated		
	Casing At 350' Pa		
	Special Hose 1" N 1 1/4 To		
	350 Circulated Cement		
	350 to Surface Inside		
	+ Out Side Casing With		
	154 Sk Cement		
	Lee Alford #12 32-33-12		

Thank You -- We appreciate your business!

Rec'd. by _____

TERMS: Account due upon receipt of services. A 1 1/2% Service Charge, which is an annual percentage rate of 18% will be charged to accounts after 30 days.

RECEIVED
AUG 30 2001
KCC WICHITA

RECEIVED
KCC District #3
AUG 28 2001
Charute <S

COPY

Company - DARLING ET AL
Farm - Jackson "D"

No. 1.

SEC. 24
NEo SE


T. 25 R. 4 E

Total Depth. 2517'
Comm. 1-24-44
Shot or Treated.
Contractor. R.J. Wixson
Issued. 4-15-44

Comp. 3-3-44

County.

Butler
KANSAS



CASING:
15 1/2" 230'
12 1/2" 935'
10" 1105'

Elevation. _____

Production. 30 B.

Figures Indicate Bottom of Formations.

cellar	8	lime	1025
shale	30	shale	1075
red rock	50	lime (sh gas 1090)	1097
lime	60	shale (HPW 1090-95)	1099
shale	85	lime	1100
gravel & sand	75	shale	1125
lime	95	lime	1130
shale	140	shale	1135
lime	175	lime	1140
shale	190	shale blue	1155
lime	195	shale	1200
shale blue	205	lime	1215
lime	210	shale	1255
shale blue	218	lime	1290
redrock	230	shale	1295
lime	275	lime hd	1305
shale	280	shale	1315
lime	310	lime	1400
shale	315	shale	1405
lime	325	lime 1 1/2 HV	1460
shale	345	shale 6HV 1450	1510
red rock	347	lime 4HV 1510	1540
lime	385	shale lime	1585
shale	400	shale	1595
lime	415	lime	1605
shale	425	shale	1650
lime	440	lime shells	1660
shale	450	shale sdy	1700
lime	460	shale	1750
shale	470	lime	1775
lime	515	shale	1800
shale	520	lime (HPW 1800-70)	1990
lime (1/2 HPW 540)	540	shale	2208
shale	555	lime	2210
shale & lime	580	shale	2215
lime	600	lime	2245
shale	625	shale	2255
lime	530	lime	2270
shale	655	shale	2345
lime	665	lime	2355
shale	675	shale	2375
lime	690	lime	2400
shale	695	shale	2415
shell & shale	705	lime	2445
shale & lime	750	shale	2450
sand	760	lime	2475
shale	785	red rock	2477
lime hd	810	shale	2515
shale	815	chat	2517
lime shell	830	Total Depth.	
shale	850		
sand	895		
lime	915		
Wtr sand	920		
lime	965		
shale	970		
lime	980		
shale	990		
lime	995		
shale	1020		

RECEIVED
AUG 30 2001
KCC WICHITA

2512 pipe set
2571 TD



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Petroleum Property Services, Inc.
155 N. Market, Ste 1010
Wichita, KS 67202-1824

September 04, 2001

Re: JACKSON #1
API 15-015-19080-00-00
NENESE 24-25S-4E, 2310 FSL 330 FEL
BUTLER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #2
130 S. Market, Room 2125
Wichita, KS 67202-3208
(316) 337-6231

Sincerely,
A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor