

LEASE NAME Vanderwork

WELL NUMBER B-1-12

4290 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 12 TWP. 32S RGE. 13 (E) or (W)

COUNTY Barber

Date Well Completed 1987

Plugging Commenced 10-2-92

Plugging Completed 10-9-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Rine Drilling and Exploration

ADDRESS 200 W. Douglas, Suite 1050, Wichita, KS 67202

PHONE # (316) 262-3418 OPERATORS LICENSE NO. 5020

Character of Well Never Produce

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-2-92 (date)

by Barlow - Dodge City (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 1/2	355	None
				4 1/2	4406	3100

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each section.

Sand from 4400 to 4190 - 4sx cement with dump bailer
BJ pumped 3 hulls, 10 gell, 50 cement, 10 gell, 1 hull, Plug - 100 cement
60-40 POZ, 6% gell

Pfiffer and Jeff Clarke on location
(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rine Exploration

STATE OF Kansas COUNTY OF Barber, ss.

Elmo Morgenstern (Employee of Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Elmo Morgenstern

(Address) Medicine Lodge, KS



SUBSCRIBED AND SWORN TO before me this 13 day of October, 19 92

Glenda Morrison
Notary Public

My Commission Expires: August 17, 1994

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1992

CONSERVATION DIVISION
Wichita, Kansas

Attachment to CP-1
Well Plugging Application Form

Rine Drilling and Exploration, Inc.
#1-12 Vanderwork "B"
API#: 15-007-22,142
150' N SW NE NE
Section 12-32S-13W
Barber County, Kansas

Plugging Procedure:

- °Dump sand up to 4190' (50' above perfs)
- °Bail in 4 sx cement on top.
- °Shoot off and pull pipe.
- °Tie on to 8 5/8", plug as follows:

300 lbs. hulls
10 sx gel
50 sx cement
10 sx gel
100 lbs. hulls
100 sx cement

Cement: 60/40 Poz, 6% gel

°Haul pipe to yard.

As proposed by Dan Goodrow by phone 9/25/92.
(District KCC)

MBR 9/25/92

RECEIVED
CONSERVATION COMMISSION
SEP 28 1992
CONSERVATION DIVISION
Wichita, Kansas