

ATE OF KANSAS
ATE CORPORATION COMMISSION
0 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-21,967-00-00

LEASE NAME Brooks-Younger

WELL NUMBER 6

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 15 TWP. 32 RGE. 13W (E) or (W)

COUNTY Barber

Date Well Completed

Plugging Commenced 7-16-03

Plugging Completed 7-18-03

EASE OPERATOR LOTUS OPERATING CO., LLC.

DRESS 914 E. Douglas Wichita, Kansas 67202

PHONE# (316) 262-1077 OPERATORS LICENSE NO. 31980

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4620'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	278'	None
				5-1/2"	4618'	2820'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from feet to feet each sack. Plugged off bottom with sand to 4000' and 5 sacks cement. Cut casing loose @2820', pulled up to 600', pumped 10 sacks gel, 50 sacks cement, pulled up to 310', pumped 50 sacks cement, pulled up to 40' and circulated 25 sacks cement to surface. 60/40 pos. 6% gel. Plugging Complete

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lotus Operating Co., LLC.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 8th day of August, 2003

[Signature]
Notary Public

My Commission Expires:



Form CP
Revised 05-

RECEIVED
AUG 11 2003
KCC WICHITA