

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NESS County. Sec. 34 Twp. 18S Rge. 21 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines. 150' SE of SE SE

Lease Owner BIRMINGHAM-BARTLETT DRILLING CO.

Lease Name PRICE Well No. 5

Office Address 300 KAUFMAN BUILDING, WICHITA, KANSAS 67202

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed SEPTEMBER 6, 1967

Application for plugging filed (VERBALLY) SEPTEMBER 6, 1967

Application for plugging approved (VERBALLY) SEPTEMBER 6, 1967

Plugging commenced SEPTEMBER 7, 1967

Plugging completed SEPTEMBER 7, 1967

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well LEO MASSEY

Producing formation Depth to top Bottom Total Depth of Well 4261 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	298'	8-5/8"	298'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug set at 435' with 80 sacks cement.
Plug set at 40' with 10 sacks cement.
Filled with mud to surface.

RECEIVED
STATE CORPORATION COMMISSION

SEP 12 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Birmingham-Bartlett Drilling Co.

Address 300 Kaufman Building, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK
Richard Hindery, partner of Birmingham-Bartlett Drilling Co., Owner, Operator, & Contractor
(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. BIRMINGHAM-BARTLETT DRILLING CO.

(Signature) By Richard Hindery Partner

300 Kaufman Building, Wichita, Kansas 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of September, 19 67.

Beverly Larson
Beverly Larson Notary Public.

My commission expires October 2, 1970.

15-135-20056-0600

PRICE "A" NO. 5 WELL

LOCATION: 150' SE of SE/4 SE/4
Section 34-18S-21W
Ness County, Kansas

SPUDDED: 8-29-67
DRILLING
COMPLETED: 9-6-67

SURFACE CASING: 8-5/8" OD 28# used casing
cemented at 298' with 170 sacks
quick set cement.

OIL STRING: None set. Dry hole.
Plugged 9-7-67.

OWNER, OPERATOR,
and CONTRACTOR: Birmingham-Bartlett Drilling Co.
300 Kaufman Building
Wichita, Kansas 67202

LOG

(Figures indicate bottom of formation)

0 -	70	Native rock
	220	Shale and clay
	250	Sandy shale
	298	Shale
	475	Shale and sand
	818	Shale and shells
	1030	Sand
	1389	Red bed and shale
	1421	Anhydrite
	2060	Shale and shells
	2535	Lime and shale
	2635	Lime
	3460	Shale and lime
	3540	Lime
	3690	Lime and shale
	4007	Lime
	4175	Lime and shale
	4180	Lime and sand
	4238	Shale and sand
	4261	Lime and shale
	4261	Rotary total depth Dry hole

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log on the PRICE "A" NO. 5 WELL as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery
Richard Hindery, Partner

Subscribed and sworn to before me
this 11th day of September, 1967.

Beverly Larson
Beverly Larson, Notary Public
My commission expires October 2, 1970.

RECEIVED
STATE CORPORATION COMMISSION

SEP 12 1967

CONSERVATION DIVISION
Wichita, Kansas